S-376
Grace Protestant Episcopal Church
Mount Vernon vicinity
public workship

1847

This Mount Vernon Episcopal church was organized in 1845 in an effort to serve the Hungary Neck residents of Somerset County living too far from All Saints Church at Monie or St. Andrews in Princess Anne. Concurrent with the formation of the church was the designation of Wicomico Parish, at the time encompassing the tenth election district.

The vestry minutes from the period indicate the initial meetings were held at the "Witch Bridge School," beginning on April 12, 1845. At the first meeting the preamble and resolutions were adopted, and the first vestry was elected. Sitting on the first vestry were Edmund Crosdale, Thomas W. Stone, Levin K. Leatherbury, Joseph B. Cottman, Isaac S. Atkinson, Alexander Jones, and William A.D. Bounds. The Reverend Meyer Lewin was approved as the church's first rector.

During the May meeting, a building committee was established which consisted of the rector, Rev. Lewin, Alexander Jones, Levin K. Leatherbury, Isaac S. Atkinson, and Edmund Crosdale. In the fall of 1845, Alexander Jones and his wife, Elizabeth, donated the church ground to the trustees, and by February of 1847, the vestry was meeting in the new church building. There is no mention of the specific craftsmen responsible for the work.

Grace Church is one of three Greek Revival style church buildings to survive in Somerset County. Unlike St. Mark's Church near Kingston (S-66) and the Joshua Thomas Chapel (S-44), Grace Episcopal Church is lighted by Gothic arched windows, and Gothic arched door openings serve as the

main and secondary entrances. Inside, the simple square-topped pews, flush board wainscoting and the vaulted ceiling contrast with the decorative altar screen and the Gothic arched door and window openings.

### **United States Department of the Interior** National Park Service

# ational Register of Historic Places Hegistration Form

This form is for use in nominating or requesting determinations of eligibility for individual properties or districts. See instructions in *Guidelines* for Completing National Register Forms (National Register Bulletin 16). Complete each item by marking "x" in the appropriate box or by entering the requested information. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, styles, materials, and areas of significance, enter only the categories and subcategories listed in the instructions. For additional space use continuation sheets (Form 10-900a). Type all entries.

1. Name of Pro	perty					
historic name	Grace Ep	iscopal	Church			
other names/site						S-376
2. Location						
street & number	Mount Vernon F	Road (MD 3	362)		N	/A not for publication
city, town	Mt. Vernon			-		X vicinity
state	Maryland code	MD	county	Somerset	code 0	39 zip code 21853
3. Classification						
Ownership of Prop	erty	Category o	f Property		Number of Re	sources within Property
X private		X building	g(s)		Contributing	Noncontributing
public-local		district			1	1 buildings
public-State		site			1	sites
public-Federal		structur	re			structures
		object				objects
_					2	1 Total
e of related m	ultiple property listin	q:			Number of cor	ntributing resources previously
		N/A	_			ational Register0
4 C4-4-/F	1.4		-			
4. State/Federa	Agency Certifica	tion				
National Register In my opinion, to Signature of certification of the In my opinion, to the In my opinion opinio	request for determine of Historic Places he property X meets with meets agency and bureau he property meets menting or other official	and meets the same does not be same does	ne procedu ot meet the PRESERV	ral and profes National Rec	sional requirements gister criteria. Se	for registering properties in the set forth in 36 CFR Part 60.  Date  Date
	gency and bureau					Date
5 National Park	Service Certificat	lion		<del></del>		
	at this property is:				<del>.</del>	
	National Register.					
	ible for the National				<del></del>	
	e continuation sheet.					
	eligible for the		<del></del>			
National Regist						
removed from t	he National Register.					
Jother, (explain:)						
			<del>-</del>	Signature of the	ne Keeper	Date of Action

6. Function or Use		S-376
Historic Functions (enter categories from instructions)	Current Fun	ctions (enter categories from instructions)
RELIGION/religious structure	RELIGIO	ON/religious structure
FUNERARY/cemetery		RY/cemetery
7. Description		
Architectural Classification (enter categories from instructions)	Materials (e	nter categories from instructions)
	foundation	BRICK
GOTHIC REVIVAL	walls	VINYL
GREEK REVIVAL		
	roof	ASPHALT
	other	WOOD

Describe present and historic physical appearance.

#### **DESCRIPTION SUMMARY:**

Grace Episcopal Church, erected in 1846-1847, is a single-story, three-bay Gothic Revival frame church on a brick foundation. The west or principal elevation is marked by a single Gothic arched double-door Each lateral side of the church is opening on the first floor. finished with three diamond-pane Gothic arched sash windows. upper portion of the window has large arched muntins that conform to the Gothic point of the window. The cornice is boxed and trimmed with a plain bed molding. The east end of the main block is largely covered by a shorter gable roofed altar and shed-roofed sacristy. On the interior, the sanctuary is divided by a center aisle with simple flush panel pews to each side. The end boards and the backs of the pews have delicate beaded boarders around each panel. The ceiling is vaulted and marked by plaster ribs. Large timber tie beams stretch across to Lighting the sanctuary are elaborate connect the side walls. Victorian chandeliers and wall sconces. Greek Revival influences can be seen in the door surrounds. Surrounding the church is a nineteenthand twentieth-century cemetery. In 1986, a single-story frame parish hall was erected west of the church and oriented on a perpendicular axis.

### United States Department of the Interior National Park Service

## **Lational Register of Historic Places Continuation Sheet**Grace Ep

Grace Episcopal Church Somerset County Maryland

S	_	3	7	6

Section number \_\_\_\_7 Page \_\_\_1

#### **GENERAL DESCRIPTION:**

Grace Episcopal Church is located on the southwest side of Mount Vernon Road three miles west of Princess Anne, Somerset County, Maryland. The single-story church faces west with the gable oriented on an east/west axis.

Erected in 1846-1847, the single-story, three-bay frame church is supported by a minimal common bond brick foundation, and the rectangular structure is sheathed with vinyl siding. In applying the artificial siding, no original exterior fabric was disturbed. The steeply pitched roof is covered with asphalt shingles. A slightly shorter gabled section extends from the east end which contains the altar and sacristy. The church cemetery surrounds the church on three sides.

The west (principal) elevation is marked by a single Gothic arched double-door opening on the first floor. The long paneled doors have Greek thumb inset moldings. The multi-pane transom has a pointed arch. Likewise, the upper gable is pierced by a Gothic arched sash window, and the gable end is trimmed with a plain bargeboard.

Each lateral side of the church is finished in a similar fashion with three diamond-pane Gothic arched sash windows. The upper portion of the windows have large arched muntins that conform to the Gothic point of the window. The cornice is boxed and trimmed with a plain bed molding.

The east end of the main block is largely covered by a shorter gable roofed altar and shed-roofed sacristy. The east gable end of the main block as well as the east end of the altar are finished with a molded cornice that defines a pediment. Pierced by a tripartite window in the east end, the altar space has slender colored glass lancet windows in each side. The one-room sacristy extends from the north side of the altar. A Gothic arched door opening marks the east side of the sacristy. A single-panel door is topped by a pointed arch transom.

### United States Department of the Interior National Park Service

## Liational Register of Historic Places Continuation Sheet Grace Ep

Grace Episcopal Church Somerset County Maryland

S-376

Section number \_\_\_7 Page \_\_\_2

The interior finishes of the church building have not been significantly altered since 1847. The sanctuary is divided by a center aisle with simple flush panel pews to each side. The end boards and the backs of the pews have delicate beaded boarders around each panel. The ceiling is vaulted and marked by plaster ribs which divide the arch in four chords. Large timber tie beams stretch across to connect the side walls. Lighting the sanctuary are elaborate Victorian chandeliers and wall sconces. Greek Revival influences can be seen in the door surrounds.

The raised altar is distinguished by a semi-circular vault and a wooden screen consisting of plain support posts, decorative brackets, and a wooden arch topped by a cross. A turned baluster altar rail separates the altar table from the main sanctuary. Opening into the sacristy is a Gothic arched door opening. The two-panel door is topped by a colored glass transom. A mid nineteenth-century box lock survives on the door with its small brass knobs. The remaining altar furniture including the pulpit, choir chairs, and altar table dates from the late nineteenth century.

Surrounding the church is a nineteenth- and twentieth-century cemetery. In 1986, a single-story frame parish hall was erected west of the church and oriented on a perpendicular axis.

Certifying official has considered the significance of this property in relation to other properties:	S-376
Applicable National Register Criteria A B XC D	
Criteria Considerations (Exceptions)	
Areas of Significance (enter categories from instructions)  ARCHITECTURE  Period of Significance  1846–1847	Significant Dates 1846-1847
Cultural Affiliation N/A	
Significant Person Architect/Builder Unknown	

State significance of property, and justify criteria, criteria considerations, and areas and periods of significance noted above.

#### SIGNIFICANCE SUMMARY

Erected in 1846-1847, Grace Episcopal Church is the earliest of the extant Gothic Revival churches in Somerset County. nineteenth century was a period of growth in Somerset County. response to this growth, several churches were built, particularly for the Methodist, who were experiencing rapid expansion in membership, and for the Episcopalians, who were reorganizing and rebuilding following a decline after the Revolution. The prevailing architectural styles utilized for these building are the Greek Revival, of which only two stand, and the Gothic Revival, which appears to have been the most commonly built. Of the Gothic Revival examples, the predominant examples exhibit the board-and-batten influence as published in <u>Upjohn's Rural Architecture</u>. Episcopal Church, however, exhibits Greek Revival overtones in the simple rectangular shape and use of decorative corner blocks in the door and window surrounds but is clearly Gothic in the steeply pitched roof and large lancet arches of the window and door openings. additional architectural significance is the integrity of the interior of Grace Episcopal Church. The interior retains nearly all of its original decorative, as well as functional, features: pews, rood screen, altar furniture, chandeliers, and sconces.

### United States Department of the Interior National Park Service

## lational Register of Historic Places Continuation Sheet Grace Ep

Grace Episcopal Church Somerset County Maryland

S-376

Section number	r <u>8</u>	Page	1
----------------	------------	------	---

#### **HISTORIC CONTEXT:**

MARYLAND COMPREHENSIVE HISTORIC PRESERVATION PLAN DATA

Geographic Organization: Eastern Shore

Chronological/Developmental Period(s):
Agricultural-Industrial Transition - A.D. 1815-1870

Prehistoric/Historic Period Theme(s):
Architecture/Landscape Architecture/Community Planning

Resource Type:

Category: Building

Historic Environment: Rural

Historic Function(s) and Use(s):
 RELIGION/religious structure
 FUNERARY/cemetery

Known Design Source: Unknown

### **United States Department of the interior**National Park Service

## lational Register of Historic Places Continuation Sheet

Grace Episcopal Church Somerset County Maryland

S-376

Section number \_\_\_8 Page \_\_2\_

#### **HISTORY AND SUPPORT:**

Grace Episcopal Church as organized in the spring of 1845 is an effort to serve the Hungary Neck residents of Somerset County living too far from All Saints Church at Monie or St. Andrew's Church in Princess Anne. Concurrent with the formation of the congregation was the designation of Wicomico Parish, at the time encompassing the tenth election district of Somerset County.

The vestry minutes from the period indicate the initial meetings were held at the "Witch Bridge School," beginning on April 12, 1845. At the first meeting the preamble and resolutions were adopted, and the first vestry was elected. Sitting on the initial vestry were Edmund Crosdale, Thomas W. Stone, Levin K. Leatherbury, Joseph B. Cottman, Isaac S. Atkinson, Alexander Jones, and William D. Bounds. The Reverend Meyer Lewin was approved as the first rector.

During the May vestry meeting, a building committee was established, consisting of the rector, Reverend Lewin, Alexander Jones, Levin K. Leatherbury, Isaac S. Atkinson, and Edmund Crosdale. In the fall of 1845, Alexander Jones and his wife, Elizabeth, donated the church ground to the vestry, and by February of 1847, meetings were held in the new building. There is no mention of the specific craftsmen responsible for the work.

In Somerset County, prominent Upjohn influenced churches are St. Paul's Episcopal Church (S-79) at Tulls Corner, built in 1848, and All Saints Church at Monie (S-355) near Venton, built in 1881.

. Major Bibliographical References	S-376
Vestry minutes of Grace Protestar present, Grace P.E. Church, Mt. Ver	
Maryland Inventory of Historic Prop Historical Trust, Annapolis, Maryl	
Touart, Paul Baker. <u>Somerset: An</u> for Maryland Historical Trust and 1990, pp 65 and 319-336.	
	See continuation sheet
Previous documentation on file (NPS):	See continuation sheet
preliminary determination of individual listing (36 CFR 67) has been requested	Primary location of additional data:
previously listed in the National Register	X State historic preservation office Other State agency
previously determined eligible by the National Register	Federal agency
designated a National Historic Landmark	Local government
recorded by Historic American Buildings Survey #	University Other
recorded by Historic American Engineering	Specify repository:
Record #	
10. Geographical Data	
reage of property <u>2.5 acres</u> USGS Quad: Monie, Maryland	
JTM References         A [1_8] [4 3_2 6_8_0] [4_2 3_2 9_0_0]         Zone Easting       Northing         C [ ] [ ] [ ] [ ] [ ] [ ] [ ] [ ] [ ]	B
	See continuation sheet
Verbal Boundary Description	
	X See continuation sheet 10.1
Boundary Justification	
The 2.5 acres included with thi of land that Grace Episcopal Church	s nomination is the current parcel and cemetery occupy.
	See continuation sheet
11. Form Prepared By	
me/title Paul Baker Touart, Architectural	Historian

Somerset County Historical Trust

P.O. Box 5

Westover

organization \_

city or town \_

street & number \_

10/14/87

(301)651-1094

Maryland zip code 21871

date \_

state \_\_

telephone \_

### United States Department of the Interior National Park Service

## **Lational Register of Historic Places Continuation Sheet**Grace Equation Continuation Sheet

Grace Episcopal Church Somerset County Maryland

S-376

Section number \_\_\_10\_\_ Page \_\_\_1\_\_

#### VERBAL BOUNDARY DESCRIPTION:

All that lot or parcel of land situate in Mt. Vernon Election District, Somerset County, Maryland, beginning for the same at a concrete post set on the west side of the State Road leading from Princess Anne to Mt. Vernon and at the northeast corner of the lot conveyed by the aforesaid grantors to Neary McIntyre and wife, from thence south 84°30' west 175 feet to another cement post, thence north 5°30' west 280.5 feet to a cement post, thence north 84°30' east 175 feet to a concrete post set on the west side of the aforesaid State Road, thence south 5°30' east 280.5 feet by and with the aforesaid State Road to the place of beginning, containing 2.5 acres more or less.

### Maryland Historical Trust State Historic Sites Inventory Form

Survey No. S-376
Magi No. 2003765408
DOE \_\_yes \_\_no

4 11				
1. Nan	1e (indicate pr	eferred name)		
historic Gra	ce Episcopal Church	1		
and/or common				
2. Loca	ation			
street & number	, SW side of Mt. Ve	rnon Road (MD 362)		not for publication
city, town Mt.	Vernon	<u>x</u> vicinity of	congressional distri	ct First
state Mary	yland	county	Somerset	
3. Clas	sification			
Category  district building(s) structure site object	Ownership public private both Public Acquisition in process being considered X not applicable	Status  occupied unoccupied work in progress Accessible yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence X religious scientific transportation other:
4. Own	er of Prope	<b>rty</b> (give names ar	nd mailing addres	sses of <u>all</u> owners)
name Trust	tees of Grace Episc	opal Church		
street & number	c/o Charles C. Che	rvenie	telephone	no.:
city, town Prin	ncess Anne	state	and zip code Md.	21853
5. Loca	ation of Leg	al Description	n	
courthouse, regi	stry of deeds, etc. Some	erset Clerk of Court		liber
street & number	Somerset County Co	ourthouse		folio
city, town Pri	incess Anne		stat	Md 21953
6. Rep	resentation	in Existing	Historical Su	
title	· · · · · · · · · · · · · · · · · · ·			_
date			federal s	etato county loca
depository for su	rvev records		iouciai S	state county loca
city, town			state	<u>e                                      </u>

### **Description**

Survey No. S-376

Condition excellent X good

fair

deteriorated ruins \_ unexposed

Check one \_ unaltered \_ altered

Check one \_x\_ original site moved

date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Grace Episcopal Church is located on the southwest side of Mount Vernon Road three miles west of Princess Anne, Somerset County, Maryland. The singlestory frame church faces west with the gable oriented on an east/west axis.

Supported by a minimal brick foundation the single-story, three-bay frame structure is sheathed with vinyl siding and covered by a steeply pitched asphalt shingle roof. A slightly shorter altar is attached to the east gable end, and a cemetery surrounds the church on three sides.

The west (principal) elevation is marked by a single Gothic arched double door opening on the first floor. The long paneled doors have Greek thumb inset moldings. The multi-paned transom has a pointed arch. Likewise, the upper gable is pierced by a Gothic arched sash window, and the gable end is trimmed with a plain bargeboard.

Each side of the church is finished in a similar manner with three diamond pane Gothic arched sash windows. The upper portion of the openings have larger arched panes that conform to the Gothic point of the window. The cornice is boxed and trimmed with a plain bed molding.

The east end of the sanctuary is largely covered by a shorter gable roofed altar and shed-roofed sacristy. The east gable end of the main church as well as the altar are pedimented. Pierced by a tripartite window in the east end, the altar has slender colored glass windows in each side elevation. The oneroom sacristy has an exterior Gothic arched door in its east side. The door has a single panel.

The interior of the church has not been altered in any significant manner since its 1847 date of construction. The sanctuary is divided by a center aisle with simple flush panel pews to each side. The end boards and the backs of the pews have delicate beaded borders around each panel. The ceiling is vaulted and marked by plaster ribs which divide the arch in four chords. Large timber tie beams stretch across to connect the side walls. Lighting the sanctuary are elaborate Victorian chandeliers and wall sconces.

The raised altar is distinguished by a semi-circular vault and a wooden screen consisting of plain support posts, decorative brackets, and a wooden arch topped by a cross. A turned baluster altar rail separates the altar table. Opening into the sacristy is a Gothic arched door opening. The two-panel door is topped by a colored glass transom. A mid nineteenth-century box lock survives on the door with its small brass knobs. The remaining altar furniture including the pulpit, choir chairs, and altar table dates from the Victorian period.

Surrounding the church is a nineteenth and twentieth-century cemetery.

8. \$	Significance	Survey No. S-2	76
_ 1500	D-1499 archeology-historic D-1599 agriculture D-1699 _X_ architecture D-1799 art D-1899 commerce	heck and justify below  community planning landscape architectur  conservation law  economics literature  education mllitary  engineering music  exploration/settlement philosophy  industry politics/government  invention	reX religion science sculpture social/ humanitarian theater transportation other (specify)
Specific	dates 1847	Builder/Architect	
check:	Applicable Criteria: A and/or Applicable Exception:		
	Applicable Exception:A	BCDEFG	
Dronens	Level of Significance:	nationalstatelocal	

Prepare both a summary paragraph of significance and a general statement of history and support.

Grace Episcopal Church is one of three Greek Revival style church buildings to survive in Somerset County. Unlike St. Mark's Church near Kingston (S-66) and Joshua Thomas Chapel (S-44), Grace Episcopal Church is lighted by Gothic arched windows, and a Gothic arch opening servés as the main entrance. In addition the interior has a mixture of Greek Revival features and Gothic Revival features. The simple square-topped pews with flush board panels and the vaulted ceilings contrast with the decorative Victorian altar screen, and the Gothic arched sanctuary door and window openings.

## 9. Major Bibliographical References

Survey No. S-376

10. Geographic	al Data			
Acreage of nominated property  Quadrangle name  Monie  ITM References do NOT comple		ences	Qu	uadrangle scale 1:24000
Zone Easting North	ing	B Zone	Easting	Northing
		D F H		
Jorbal boundary description and	a iustilicativii			
		apping state or	county bou	
List all states and counties for		apping state or	county bou	ndaries code
List all states and counties for state	properties overl		county bou	
List all states and counties for state	properties overl code code	county	county bou	code
List all states and counties for state  state  11. Form Prepa	code code	county	county bou	code
	code code red By	county county storian		code
List all states and counties for state  state  11. Form Prepa  name/title Paul Touart - Arch	code  code  red By  hitectural Hi istorical Tru	county county storian	12/	code

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust

Shaw House 21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

GRACE EPISCOPAL CHUNCH VESTRY MINUTES - WILDMICO PARISH

VESTRY MINUTE Brose 1845 - 1962

P. 1 WITCH BRIDGE SCITTOR HOUSE, HUNGARY APRIL 12, 1845

PREAMBLE AND RESOLUTIONS ADOPTED

FOR OGANIZATION OF A SEPARATE

PROTESTANT EPISCOPAN CHUICH, N

THE TENTO ETETON DISTRICK OF

SOMENSET COUNTY - "UNDER THE NAME

ON GRACE CHNICH HUNGAMY NECK

MESSAS EDMUND CROSDAVE
AND IS ARE S. ATKINSON WERE APPOINTED
TELLERS UPIN COUNTING THE BALLUTS
THE FOLLOWING GENTEMEN WILL

ELECTED EDMUND CRUS DATE
THOMAS W. STONE
LEVIN K. LEATHER BURY
JOSEPH B. CUTTMAN
(SAAC S. ATKINSON
GEORGE JONES
MEXANDER JONES
WILLIAM A. D. BOUNDS

p. 6. AMAIL 12, 1845, THE ROV. MOYEN LEWIS (?) LEWIN

ALLEMANDER SONES AND LEVEN M. LEWIN, PLEXANDER SONES AND LEVEN K. BEARTERBURY (SAME 5 ATTLINSON, EDMUND CRUSDATE

WIRE ELECTED A BUILDANG

P. G. JANUAMY 11, 1846 THE ROVENEND JAMES CIMPOINSE MAN DR. L. W. STONE NEME PLACED UPON TITE BULLDING COMMITTER IN LIEM OX ME PON'ND M. LEWIN AND LEVIN K. LEATHORSUM RESIGNEM.


CHE CONGRETARION OF GRAVE.
CHECK, HUNGARY NECK, APRIL 6, 1846

MINUTES HEMPING PHANCIES FROM
"WITH BRIDGE SUTTOR" TO GRACE
CHUNER" - FEBRUARY 1, 1847.

p. 16 Mm, 29, 1847 - ORGANIZATION AND METER prop Brushs of WICOMICO PARISM

Poroni Gues Hore Burt summen 1910 -"

10 2010 HOWN FOR CHURCH - OCTOBERC 4, 1845 freezement fores min Eliz. Ins wire 62' bornen comm-




#### **United States Department of the Interior** National Park Service


## . lational Register of Historic Places Continuation Sheet

Grace Episcopal Church Somerset County Maryland S-376

Section number \_\_\_\_10 Page \_\_\_\_2










Grace Episcopal Church

tt-Vernon Somerset Co. Md.

Northeast Elevation
3/86, Paul Touart, Photographer
Neg/Md. Historical Trust



Grace Episcopal Church Mt. Vernon, Somerset Co. Md. Northeast Elevation 3/86, Paul Touart, Photographer Neg/Md. Historical Trust



Grace Episcopal Church
Mt. Vernon, Somerset Co. Md.
Southeast Elevation
3/86, Paul Touart, Photographer
Neg/Md. Historical Trust



Grace Episcopal Church
Mt. Vernon, Somerset Co. Md.
Interior
3/86, Paul Touart Photographer
Neg/Md. Historical Trust



Grace Episcopal Church S-376 Mt. Vernon vicinity, Somerset Co., MD Interior 11/85, Paul Touart, Photographer Neg./ MD Hist. Trust





Grace Episcopal Church S-376 Mt. Vernon vicinity, Somerset Co., MD Interior - Gothic Revival Door 11/85, Paul Touart, Photographer Neg./MD Hist. Trust



S-376

Grace Episcopal Church
Mt. Vernon, Somerset Co. Md.
Northeast Elevation
3/86, Paul Touart Photographer
Neg/Md. Historical Trust




Grace Episcopal Church S-376 Mt. Vernon, Somerset Co, Md. Church Pew. 3/86 Paul Touart, Photographer Neg/Md. Historical Trust



Grace Episcopal Church S-376 Mt. Vernon, Somerset Co. Md. Oil Lamp 3/86, Paul Touart, Photographer Neg/Md. Historical Trust





Grace Episcopal Church S-376 Mt. Vernon, Somerset Co. Md. Front Door 3/86, Paul Touart, Photographer Neg/Md. Historical Trust